

# 115/34.5kV Solar Power Plant & Substation Design Team 18 - May 2024 Lightning Talk #2 - Project Plan

Baylor Clark, Liam Grossman, Eduardo Jimenez-Tzompaxtle, Siti Mohd Radzi, Elymus Schaffer, Chicheng Tang





Due to increasing Renewable Energy requirements for utilities, a 34.5/115 kV distribution substation and 60 MW Solar Plant will need to be designed by Iowa State University. We as the project team are responsible for the complete design of solar layout, electrical layout, and associated construction deliverables. Our project team will also perform various calculations required of a typical substation, including load-flow analysis, short-circuit studies, system protection design, and grounding calculations.

#### **Substation Overview**

Transmission lines come into substation at 115 kV. These lines then step down into transformers which take the voltage from 115 kV to 34.5 kV. The line then goes through a switchgear to help service in case of a disaster. After the switchgear, the lines go to bus bars which help distribute the voltage to different lines to be distributed.







The circuit diagram to the left shows an overview of a typical substation circuit. This shows a 33/11 kV system and transformer, but similar principles apply to our project.

#### Electricity Infrastructure – Solar Farms (PV systems)



- Solar Farms (Photovoltaic systems) are usually interconnected to the grid at either the sub-transmission voltage or primary distribution level.
- Solar systems provide a DC output that must be inverted and stepped-up before making a network (grid) interconnection.

#### Safety Moment - Importance of Regular Breaks

WH

- Both Mental and Physical Benefits
- Breaks help boost overall productivity
  - Pushing through work can lower performance
- Prevents decision fatigue and reduces possible errors
- Neglecting breaks can lead to burnout
- Study on Duration of Breaks
  - Shorter more frequent breaks in the morning
  - Longer breaks in afternoon and evening

#### ARE YOU TAKING ENOUGH BREAKS DURING THE WORK DAY?

IAT CAN HAPPENS WHEN YOU <u>DON'T</u> TAKE BREAKS	WHAT HAPPENS WHEN YOU DO TAKE BREAKS
CHRONIC PAIN	IMPROVE YOUR PRODUCTIVTY
CARDIOVASCULAR DISEASE	OWERS STRESS LEVELS
W HIGHER STRESS LEVELS	
PROBLEMS WITH CREATIVITY	REDUCES ANXIETY
✓ AT RISK FOR BURNOUT	
MORE ERRORS IN WORK	INCREASE ENERGY LEVELS

Baylor



# **Project Plan**

#### Task Decomposition



## Project Management Style - Waterfall

- Waterfall Management Style emphasizes the completion of certain phases of design before moving on to the next phase
- Each semester will follow a waterfall methodology from design to maintenance phase
  - Additionally, an overarching waterfall methodology will be used across both semesters
- Our gantt chart was modeled to emulate this waterfall methodology



## **Project Milestones**

- Research Equipment
  - Collect 3 data sheets for PV panels, combiner boxes, and solar inverters
  - Research necessary components and present our understanding of them
- Select Components
  - Finalize component selection
  - Find appropriate location for construction
- Array Parameters
  - Use array calculation tool to select solar farm sizing (number of panels, combiner boxes, inverters, ect)
  - Component numbers and arrangement should result in an AC output of 60 MW and a DC to AC ratio of approximately 1.3
  - Component costs will be calculated to provide overall array cost
  - Voltage drop calculations will be done to provide realistic power loss statistics
- Design Solar Array (AutoCAD)
  - Solar array will be designed in AutoCAD based on array calculation tools
  - A professional title block will be created for array drawings
- Solar Farm Simulation
  - The solar farm will be set up within a simulation software (ETAP)
  - The power flow of the solar farm will be simulated
  - Array parameters will be checked and adjusted to ensure all necessary deliverables are met

# Project Timeline/Schedule

#### FALL 2023 - SOLAR POWER PLANT DESIGN



## Gantt Chart - Fall 2023

PROJECT TITLE

PROJECT TIT	'LE	[115/34.5KV	/ Solar Pow	ver Plant & S	ubstation]		COMPAN	Y NAME	[BI	ack & Veat	tch]																					
PROJECT MA	NAGER	[Adam Schroed	der, Michael M	(cdonald)			DATE		9/	12/23																						
WBS NUMBER	TASK TITLE	TASK OWNER	START DATI	E DUE DATE	DURATION	PCT OF TASK COMPLETE	WE	EK 1	PHASE	ONE K 2	WEE	EK 3	WEE	X 4	PHASE 1	TWO	WEEK	WEEK 7	PHASE T	HREE	WEI	EK 9	VEEK 10	E I	PHASE	FOUR	v N T	/EEK 12	W	EEK 13	F	HASE FIVE WEEK 14
1	Documentation																												m		m	
11	Weekly Agenda	Baylor *	08/30/2023	3			1				1	,			1		1															
1.2	Meeting Minutes	Bell *	08/30/2023	3		ä									· ·																	
13	Bi-weekly report	Eli 🔹	08/30/2023	9		ä																										
1.4	Presentation Slides	ALL	08/30/2023	3		ä																										
1.5	Project Design Document (Preamble	ALL	08/30/2023	3		ī																										
16	Final Report	All				ä																										
2	Research					-																										
-	Data abast I bility DV Calas Danal	11	0/12/22	0/20/22		_																										
21	Data sneet Utility PV Solar Panel	Liam •	9/12/23	9/20/23		H																										
2.2	Safety Moment	Ell +	9/12/23	9/20/23		H																										
2.3	Data sheet for Combiner Box	Eduardo +	9/12/23	9/20/23																												
2.4	Data sheet for Inverter	g -	9/12/23	9/20/23																												
2.5	power plant	Bell 👻	9/12/23	9/20/23																												
2.6	Substation Design	Baylor	9/12/23	9/20/23																												
3	Component Selection																															
3.1	Material components lists	-	9/14/23	9/20/23																												
3.2	Location	•	9/14/23	9/20/23																												
3.4	Substation Component (Main, and bus)	•	9/14/23	9/20/23																												
4	Array Parameter Calculation																															
4.1	String size		9/20/23	10/4/23																		1.1		1.1				101 1	111			TERM
4.2	Electrical rack size	-	9/20/23	10/4/23																												
4.3	CB capacity		9/20/23	10/4/23																												
4.4	Array design	-	9/20/23	10/12/23																												
4.5	Array size	*	9/20/23	10/12/23		ā																										
4.6	Total equipments	*	9/20/23	10/12/23																												
4.7	Total cost and budget		9/20/23	10/12/23																												
4.8	Total Power (AC & DC)	-	9/20/23	10/12/23																												
4.9	Voltage drop calculation		9/20/23																													
5	Designing Solar Panel (AutoCA	D)																														
5.1	Solar Panel (key plan, elevation, grounding)			11/2/23																												
5.2	Array			11/2/23																												
5.3	Rack	•		11/2/23																												
5.4	Solar Layout	•		11/2/23																												
5.5	Solar Field Design	•																														
6	Simulation																															
6.1	Designing Solar Power System			11/23/23																												
6.2	Assign requirements and unive	-		11/23/23																												
0.2	Assign requirements and value			11/00/00																												
6.3	Simulation	*		11/23/23																												

# Gantt Chart - Spring 2024

#### **GANTT CHART**

PROJECT TITLE	[115/34.5KV Solar Power Plant & Substation]	COMPANY NAME	[Black & Veatch]
PROJECT MANAGER	[Adam Schroeder, Michael Mcdonald]	DATE	1/29/24

									PHASE ONE			PHASE TW	0				HASE FOUR		PHASE FIV							
WBS NUMBER	TASK TITLE	TASK OWNER	START DATE	DUE DATE	DURATION	PCT OF TASK COMPLETE	WEEK		WEEK 2	WEEK 3	WEEK 4	WEEK 5		EEK 6	WEEK 7	WEEK 8		WEEK 9			WEEK 11	WEEK 1		WEEK 1		WEEK 14
							M T W	RFM	TWRF	MTWR	FMTWR	FMTW	FMT	WRF	MTWR	FMTW	RFM	TWR	M T W	R F M	T W R F	M T W	RF	M T W	RFI	MTWR
1	Documentation																									
1.1	Weekly Agenda	•																								
1.2	Meeting Minutes	*																								
1.3	Bi-weekly reports	Ψ.																								
1.4	Presentation Slides	*																								
1.5	Project Design Document (Preamble)	*																								
1.6	Final Report																									
2	Initial Research																									
2.1	Substation Component	•																								
2.2	Safety Moment	*																								
2.3	One-line diagram of substation																									
2.4	Substation Design																									
2.5	Presentation Slides	•																								
3	Component Selection																									
3.1	Bus and line																									
3.2	Main Component																									
3.3	Component Spec																									
3.4	Substation Component (Main, and bus)																									
4	Calculation																									
4.2.1	DC battery calculation																									
4.2.2	Grounding calculation	-				ā																				
4.3	AC load calculation	*																								
4.4	Lightning calculation	*				Ē																				
4.3.1	Total equipment	*				ū																				
4.3.2	Total cost																									
4.3.3	Total Power (AC & DC)	*																								
5	Designing																									
5.1	One-line diagram of substation	•																								
5.2	Bus plan																									
5.3	Grounding diagram																									
5.4	Conduit diagram					ā																				
5.4.1	Whole Solar and Substation Layout																									
6	Simulation (ETAP)																									
6.1	Designing Solar Power System	•																								
6.2	Assign requirements and value																									
63	Simulation	-																								
0.0	onnuduvn					_																				

## **Risks/Risk Management**



- 1. Technical Risk
  - a. Technology selection
  - b. System Design
- 2. Land and Site Risk
  - a. Land Acquisition
  - b. Site Condition
- 3. Construction Risk
  - a. Project Delays
  - b. Cost
- 4. Financial Risk
  - a. Financing Issues
- 5. Policy Risk
  - a. Permit and Approvals
  - b. Government Policies Changes